



## **Daikin Heat Pump VRF Special Notes**

### **TO AVOID ISSUES PLEASE READ IMPORTANT NOTES :**

Please note it is critical to perform the following field setting changes on Daikin Heat Pump VRF units prior to the application of MyAir. Failure to complete these field settings will lead to significant issues with operation which is not covered by warranty.

#### **FIELD SETTINGS**

The field setting for the Master unit is 22-9-02 and the field setting for the Slave/s is 22-9-01.

It is important to have the control box with the touch screen connected to be the Master unit please.